BRUHATH BANGALORE MAHANAGARA PALIKE,

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/OW/WORK_INDENT50861

Name of Work: Repairing work Range office Building, removal of debries and providing new precast RCC covering slabs desilting of drains in ward no.12 Shettuhalli

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri SHIVANANDA N	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Providing skilled labour (mazdoor Heavy)for removal of debris, slabs resetting,desilting of drains and other ward maintainence works. (Pg No -LVI, & Itm No 5)	Day	1080.00	475.20	Rupees Four Hundred Seventy Five and Twenty Paise Only
2	Hire charges of Tractor 40HP including cost of driver, Fuel and other incidental charges. (Pg No-XLVIII, Sl. No.19)	Day	90.00	1201.32	Rupees One Thousand Two Hundred One and Thirty Two Paise Only
3	Hire charges of JCB excavator including cost of driver, Fuel and other incidental charges. (Pg No-XLVIII, Sl. No.23)	Day	120.00	6065.18	Rupees Six Thousand Sixty Five and Seventeen Paise Only
4	Removing and Re Setting of Footpath slabs (PWD SR 2018-19 P.No: 270, I.No.: 37.56)	Sqm	450.00	222.39	Rupees Two Hundred Twenty Two and Thirty Nine Paise Only
5	Providing and laying 25cm thick Pre Cast Cover slabs including cost of all materials, labours, curing, transportation, loding unloding etc.., complete as per the direction of Engineer in charge.	Sqm	18.00	5770.17	Rupees Five Thousand Seven Hundred Seventy and Seventeen Paise Only
6	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge (Data Rate)	Sqm	110.16	2488.91	Rupees Two Thousand Four Hundred Eighty Eight and Ninety Paise Only

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,

7	Providing SS pipe name boards-made of 2" (65mm) dia SS pipe for vertical pole and 3no of horizontal support pipe of 11/2" dia. pipe each of length 1.00 mtr sinage board of size 60x45cm and 60x23cm size made of 16 guage SS sheet welded to SS tube frame of size 25x25 mm all manual are cut size and all items electricals welded as per the drawing all Joints are grainded smooth and pasted along with the sticker printed the name of the road and name of the elected mambers fixed to ground in 1 : 2 :4 with PCC at the bottom, all cost inclusive of lead a nd lifts Chapter, 530.0	No	58.00	23795.25	Rupees Twenty Three Thousand Seven Hundred Ninety Five and Twenty Five Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Executive Engineer